

Olmstead Dam, U.S.A.

Contractor—W.G.A.

Owner—Army Corps
2010

The river control structure and locks are being replaced using a system of float in and placement of precast elements to form a high quality underwater structure. A key element of the system is the formation of joints and seals between the elements.



proserve
MARINE CONSTRUCTION ENGINEERS

Proserve Ltd.

80 Priory Road,
Kenilworth,
Warwickshire, CV8 1LQ,
England

UK: 01926 512222
Int: 00 44 1926 512222
office@proserveltd.co.uk
www.proserveltd.co.uk

Fabriform



Pier Shell Lift

Location

For the control gate section of the structure, concrete base shells and pier shell caissons are precast, lifted and positioned into place by a purpose made floating crane barge suitable for river use. Proserve designed, tested and supplied appropriate grout bag systems.



Vertical Seal Test



**Condensed Grout Bag Base Seals
Under a Pier Shell Caisson (Blue)**

Prefixed vertical grout bag seals are used to create sealed compartments under the base shells for tremi concrete infill.

Grout bag base seals are used to the pier shell for subsequent tremi concrete infill. The seals are condensed with break covers which fail when grouted, but withstand accelerated local flow to 15 ft/ s. The condensed seals are prefixed within a protective recess. The grout filling process is automated with filling hoses taken to the surface and grout sensors used in the venting system.